



NOTES:

1. PORTLAND CEMENT CONCRETE SHALL ATTAIN A 28-DAY COMPRESSIVE STRENGTH OF 3300 P.S.I..
2. CONTRACTION JOINTS SHALL BE PLACED AT 15 FOOT MINIMUM INTERVALS WITH 1 1/2" DEPTH. MATCH SIDEWALK JOINTS.
3. PLACE CONTRACTION JOINT IN CURB OVER CENTER OF PIPE EXTEND PIPE TO BACK OF SIDEWALK IF SIDEWALK IS ADJACENT TO CURB.
4. DRAINAGE BLOCKOUT 3" I.D. PLASTIC PIPE W/BELL. LOCATED AS DIRECTED IN THE FIELD. GENERALLY NOT LESS THAT 2 PER LOT.



City of Astoria
Public Works Department
 1095 Duane Street

Curb Detail

Date Adopt. 11/01/12

Date Rev. ----

DWG. NO.

ST-4

Dwg. Name: ST-4 Curb.dwg